

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1188

LIBER 314 PAGE 1269

For corners in Missaukee
(County)

Located In:

Corner Code #

- | | | |
|--------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>23N</u> R <u>7W</u> | <u>M-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

MISSAUKEE COUNTY MICHIGAN

RECORDED NOV 10 1997 4:30 PM

Carolyn Flare
 REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, J. Dean Geers, in a field survey on June, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-5) 1838 GLO Section Post by John Brink, Deputy Surveyor; Yellow Pine 18-S50W-30, White Pine 8-N5½W-44
- M-5) 1889 County Survey Notes; Perpetuated Corner by driving piece of Norway limb 2' long and 3" diameter level with surface and filling around stake with broken boulders.
- M-5) 1895 Richardson Survey in Section 7, T23N, R6W; Norway Pine Stake with Broken Boulder; No witnesses given
- M-5) 1991 Case LCRC, Liber 1, Page 828; Found 1¼" diameter Pipe and one remaining GLO Pine Stump Witness S50W-18-Red Pine Stump-19.8, N15W-12" Poplar-41.53, S25E-24" Red Pine-8.11, S25W-Twin 8"Oak-42.45
- M-5) 1997 DNR LCRC, Liber 1, Page 1134; Found and accepted Pipe as recorded in Liber 1, Page 828; 18" Red Pine Stump-S50W-19.8, 24" Red Pine-S25E-8.11, 8" Twin Maple-S34W-42.45, 16" Red Pine-N45W-35.29, 4" Maple-N57E-30.88

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-5) Section Corner common to Sections 12 and 13, T23N, R7W, and Sections 7 and 18, T23N, R6W. Found 1¼" diameter Pipe as recorded in Liber 1, Page 828 and 1134. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-5) Set Missaukee County Monument on existing Iron
 - S25E 8.02 24" Red Pine
 - NG0E 30.91 6" Maple
 - N40W 35.30 18" Red Pine
 - S35W 42.42 10" Twin Maple

SURVEY & REMONUMENTATION

Peer Group Reviewed and Approved

Date: 10-29-97

J. Dean Geers
 J. Dean Geers, Missaukee Co. Representative

JAN 16 1998

SECTION

Signed by [Signature]

Date 11-6-97

Surveyor's Michigan License No. _____

