

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

# 1189

Missaukee Located In: Corner Code #  
 (County)

1. Public Land Survey T23NR 7W M-6  
 T R  
 T R  
 T R

2. Property Controlling S T R  
 in Section S T R

3. Miscellaneous S T R  
 Property in Sec. S T R

LIBER 314 PAGE 1270

MISSAUKEE COUNTY MICHIGAN

RECORDED NOV 10 1997 4:30 PM

*Carolyn Flare*  
 REGISTER

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, J. Dean Geers, in a field survey on June, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- M-6) 1838 GLO Quarter Section Corner by John Brink, Deputy Surveyor; Yellow Pine 16-S25W -33, White Pine 24-N82W-14
- M-6) 1991 Case LCRC, Liber 1, Page 829; Found 1½" diameter Pipe which fits distances and alignment along Township Line; S50W-5" Maple-27.16, S40E-4" Poplar-15.62, North-10" Maple-13.90
- M-6) 1997 DNR LCRC, Liber 1, Page 1135; Found and accepted Pipe as recorded in Liber 1, Page 829; 5" Balsam-S54E-27.90, 8" Maple-N83W-35.45, 10" Maple-North-13.95, 4" Poplar-S40E-15.65, 5" Maple-S50W-27.15

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-6) Quarter Section Corner common to Section 13, T23N, R7W and Section 18, T23N, R6W. Found 1½ Pipe as recorded in Liber 1, Page 829 and Page 1135. Corner is ±40' Northerly of trail. This corner is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-6) Set Missaukee County Monument and Iron in existing Pipe
 

North	13.97	12" Maple
S45E	15.61	6" Poplar
S55W	27.15	6" Maple
N80W	35.49	8" Maple
N30W	34.95	

Peer Group Reviewed and Approved

Date: 10-29-97  
*J. Dean Geers*  
 J. Dean Geers, Missaukee Co. Representative

**SURVEY &  
 REMONUMENTATION**

JAN 16 1998

Signed by \_\_\_\_\_ Date 11-6-97  
 Surveyor's Michigan License No. 33977 SECTION \_\_\_\_\_

