

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Missaukee Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey	T <u>23N</u> R <u>7W</u>	<u>M-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

# 1191  
 LIBER 314 PAGE 1272  
 MISSAUKEE COUNTY, MICHIGAN  
 RECORDED NOV 10 1997 4:30 PM  
*Carolyn Flare*  
 REGISTER  
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, J. Dean Geers, in a field survey on June, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

M-8) 1838 GLO Quarter Section Post by John Brink, Deputy Surveyor; Cedar 16-S44W -13, Cedar 14-N50W-12

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M-8) Quarter Section Corner common to Section 24, T23N, R7W and Section 19, T23N, R6W. Re-established Corner on Township line at proportionate distance between Found Northeast Corner and Southeast Corner of Section 24. This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-8) Set 1/2" Iron and Missaukee County Monument  
 S55W 27.33 10" Cedar  
 S55E 11.96 14" Cedar  
 N55W 26.20 5" Twin White Birch  
 N75E 1.22 3" Balsam

Peer Group Reviewed and Approved

Date: 10-29-97  
*J. Dean Geers*  
 J. Dean Geers, Missaukee Co. Representative

**SURVEY &  
 REMONUMENTATION**

JAN 16 1998

SECTION \_\_\_\_\_

Date 11-6-97

Signed by \_\_\_\_\_

Surveyor's Michigan License No. \_\_\_\_\_

