

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

# 1192

For corners in

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23NR</u> 7W	<u>M-9</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

LIBER 314 PAGE 1273  
 MISSAUKEE COUNTY MICHIGAN  
 RECORDED NOV 10 1997 4:30 PM  
*Paula K. Klose*  
 REGISTER  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, J. Dean Geers, in a field survey on June, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- M-9) 1838 GLO Section Post by John Brink, Deputy Surveyor; Cedar 14-S23W-27, Cedar 10-N54W-16
  - M-9) 1975 McClung LCRC, Liber 1, Page 176; Set Corner by prorating Township line, 10" Cedar-N45E-6.9, 12" Cedar-N55W-36.3, Beaver Dredge-North-18.0
  - M-9) 1997 DNR LCRC, Liber 1, Page 1143; Found and accepted steel fence post as recorded in Liber 1, Page 176; 3" Balsam-S34W-18.56, 2" Spruce-N40E-12.18, Cedar-S58W-28.12, 12" Cedar-N65W-36.78, 10" Cedar-N50E-7.15

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- M-9) Section Corner common to Sections 24 and 25, T23N, R7W and Sections 19 and 30, T23N, R6W. Found Steel Fence Post as recorded in Liber 1, Page 176 and 1143. This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


- M-9) Found Steel Fence Post and added 5/8" x 36" Rerod with Missaukee County Monument
  - N50E 7.12 12" Cedar (dead)
  - N45E 12.21 3" Balsam
  - S34W 18.52 4" Balsam
  - S56W 28.08 14" Cedar (dead)
  - N65W 36.77 12" Cedar (dead)

**SURVEY & REMONUMENTATION**

Peer Group Reviewed and Approved  
 Date: 10-29-97  
*J. Dean Geers*  
 J. Dean Geers, Missaukee Co. Representative

JAN 16 1998

Signed by *J. Dean Geers*  
 Surveyor's Michigan License No. 33977



Date 11-6-97