

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

#1193

For corners in

Missaukee Located In: Corner Code #
 (County)

1. Public Land Survey T23NR 7W M-10
 T R
 T R
 T R

2. Property Controlling S T R
 in Section S T R

3. Miscellaneous S T R
 Property in Sec. S T R

LIBER 314 PAGE 1274

MISSAUKEE COUNTY MICHIGAN

RECORDED NOV 10 1997 4:30 PM

Roslyn Flare
 REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, J. Dean Geers, in a field survey on June, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- M-10) 1838 GLO Quarter Section Post by John Brink, Deputy Surveyor; White Pine-7-S29W-18, White Pine-N39½W-22
- M-10) 1975 McClung LCRC, Liber 1, Page 176; Set 5/8" Rod/cap on line and equal distance. 14" Norway Pine-S05W-49.5, 12" Norway Pine-S60W-57.0, 6" Maple-N25E-41.2'
- M-10) 1987 McClung Survey S-1, Page 319; Found Corner as recorded.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-10) Quarter Section Corner common to Section 25, T23N, R7W and Section 30, T23N, R6W. Found 1" Pipe as recorded in Liber 1, Page 176. This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-10) Found 1" Pipe and added 5/8" x 36" Iron and Missaukee County Monument
 - N35E 21.61 6" Twin Maple
 - S12E 24.81 16" Red Pine
 - S25W 52.52 6" White Pine
 - N80W 65.43 8" Maple clump


Peer Group Reviewed and Approved

Date: 10-29-97
J. Dean Geers
 J. Dean Geers, Missaukee Co. Representative

SURVEY & REMONUMENTATION

JAN 16 1998

Signed by _____
 Surveyor's Michigan License No. _____



Date 11-6-97

SECTION