

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Missaukee
 (County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------------------------|-------------|
| 1. Public Land Survey | T <u>23</u> N R <u>7</u> W | <u>M-12</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

#1195
 LIBER 314 PAGE 1276

MISSAUKEE COUNTY MICHIGAN
 RECORDED NOV 10 1997 4:30 PM
Carolyn Flare
 REGISTER
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, J. Dean Geers, in a field survey on June, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-12) 1838 GLO Quarter Section Post by John Brink, Deputy Surveyor; Sugar 8-S69W-20, Hemlock 13-N39W-36
- M-12) 1914 Beuthien Survey in Section 31, T23N, R6W; Stone, Elm 7-N62½E-71, Elm 7-N38W-94
- M-12) 1987 Wilcox LCRC, Liber 1, Page 780; Set Iron next to two stones; old fence to South and East; Retracing Beuthien Survey of 1914; S68E-179.94-24" Maple, S27E-154.59-36" Maple, S05E-175.27-24" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-12) Quarter Section Corner common to Section 36, T23N, R7W and Section 31, T23N, R6W. Found Iron as recorded in Liber 1, Page 780. This corner is accepted as a careful and faithful re-establishment on the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-12) Found Iron and replaced with 5/8" x 36" Rerod and Missaukee County Monument


N11E	50.95	6" Red Pine
S15E	94.63	4" Cherry
N45E	35.54	8" Red Pine
N84W	160.30	12" Cherry

SURVEY & REMONUMENTATION

Peer Group Reviewed and Approved
 Date: 10/29/97
J. Dean Geers
 J. Dean Geers, Missaukee Co. Representative

JAN 16 1998

Signed by _____
 Surveyor's Michigan License No. 33977



SECTION

Date 11-6-97