

# 1023

JAN 30 1996

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

MISSAUKEE COUNTY MICHIGAN

For corners in  
Missaukee

(County)

Located In:

Corner Code #

RECORDED JAN 2 1996 1:15 P

*John Klare*  
REGISTER

Register of Deeds Stamp & File Number

1. Public Land Survey	T	23	R	7	M-13
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Sec.	S		T		R
	S		T		R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel E. Schripsema in a field survey on August, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-13) 1837 GLO post by John Brink, Deputy Surveyor Hemlock 12 N55°E 34, Maple 14 N55°W 21
- M-13) G.S.Gullikson Field book page 47
- M-13) 1898 E.A.Beuthien, Co. Surveyor notes Book 33 page 64. WPS 28, N28 1/2 feet Tel Pole, S30E 22 1/2 ft
- M-13) 1914 E.A.Beuthien, Co. Surveyor notes Book 34 page 56. Old corner, Cedar Stake WPS N42 links, WPS N7W 27, Tel Pole S30E 33, Tel Pole S20E 23.  
(continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-13) Section corner common to T 22 & 23 N, R 6 & 7 W.

Found cabin spike in centerline M-55, centerline drive to South, and 25' East of old fence to South. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-13) Placed Brass Missaukee County Monument on 1/2" iron in Mon. Box with #24617 at original location.

- \*N34°E 58.57 12" Poplar
- N01°W 49.36 4" square ROW Marker
- S26°W 56.04 4" square Row Marker
- S33°W 76.15 8" twin Maple
- S25°E 116.33 NW Cor. Garage
- \* = Fd. witness nail

Peer Group Reviewed and Approved

Date: 1-2-96  
*J. Geers*  
J. Geers, Missaukee Co. Representative

Signed by: Daniel E. Schripsema Date: 12-29-95  
Surveyor's Michigan License No. 24617