

JAN 19 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 330 PAGE 604

For corners in

Missaukee  
(County)

Located In:

Corner Code #

#1320

MISSAUKEE COUNTY MICHIGAN

RECORDED AUG 19 1999 <sup>15</sup> P.M.

*Pauline Flare*  
REGISTER

Register of Deeds Stamp & File Number

1. Public Land Survey	T <u>24N</u> R <u>5W</u>	<u>M-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Marvin E. Myers, in a field survey on March, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2	8		5		4		3		2		1	
3												
4	7		6		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1839 John Brink, DS Mon - Post Wit: 10" B. Oak N66°W 10 lks. 10" W. Oak N38°E 20 lks.	Marcus Schaaf 1940's Mon: Iron Set  LCRC L1 P 199 Missaukee Co. Records Sept 17, 1974 Herbert L. Fluharty #18223
G.L.O. - Aug 1852 Geo. H. Cannon, DS Mon - Post Wit: None given	Mon - 1 1/2" pipe Wit: 14" Oak S72°W 59.85 15" Oak S44°E 58.00 8" R. Pine N28°E 69.75

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Schaaf 1 1/2" pipe in concrete. Found 18" Norway N35°E 69.64  
Accepted pipe as the best available evidence of the position of the Original Corner. Replaced pipe with Standard Crawford County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Standard Crawford County Corner 0.5' below surface.  
Wit: Nail E. side 18" Norway N35°E 69.64  
Carsonite Post N67°E 46.26  
Nail S. side 16" Twin Maple S55°E 74.84  
Nail N. side 7" B. Oak S76°W 66.86



Peer Group Reviewed and Approved

Date: 8-5-99

*J. Dear Geers*  
J. Dear Geers, Missaukee Co. Representative

Signed by Marvin E. Myers

Date June 1, 1999

Surveyor's Michigan License No. 31600