

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
MISSAUKEE  
(County)

Located In: \_\_\_\_\_ Corner Code #/# \_\_\_\_\_

- |                                    |   |            |   |           |               |
|------------------------------------|---|------------|---|-----------|---------------|
| 1. Public Land Survey              | T | <u>24N</u> | R | <u>6W</u> | <u>K-12</u>   |
|                                    | T | _____      | R | _____     | _____         |
|                                    | T | _____      | R | _____     | _____         |
|                                    | T | _____      | R | _____     | _____         |
| 2. Property Controlling in Section | S | <u>36</u>  | T | _____     | <u>10, 11</u> |
|                                    | S | _____      | T | _____     | _____         |
| 3. Miscellaneous Property in Sec.  | S | _____      | T | _____     | _____         |
|                                    | S | _____      | T | _____     | _____         |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, CARL F. ROSER, in a field survey on SEPTEMBER 13, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

<u>K-12</u>	<u>10</u>	<u>11</u>
-------------	-----------	-----------


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<u>K-12</u>	<u>10</u>	<u>11</u>
FD NARROW GAUGE RR IRON FOR E 1/4 COR SEC 35 AS CALLED FOR BY CO SURVEYOR E.A. BEUTHIEN IN 1891-1909 SURVEY NOTES. CTR OF GRAVEL RD IN CURVE, NW-SE, IS EAST 160'.	SET NW COR OF SW 1/4 OF SW 1/4 OF SEC 36 PER STANDARD BLM INSTRUCTIONS. CTR OF N-S TRAIL IS 139'± EAST.	ESTABLISHED CTR SW 1/4 SEC 36 PER STD BLM INSTRUCTIONS. CTR OF RD IS 197'± N. N-S FIELD BERM IS 3'± W. LOOKING TO S, OLD N-S FN REMAINS IS 3'± 2' W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>K-12</u>	<u>10</u>	<u>11</u>
FD RAILROAD RAIL; ADDED CED POST W/LOC TAG & STONES.	DROVE 5/8" X 34" REROD W/RLS CAP. SET CED POST W/LOC TAG.	DROVE 5/8" X 34" REROD W/RLS CAP. SET CED POST W/LOC TAG.
POWER POLE N65°W 2.48'	3" MAPLE N15°W 12.8'	SE COR HOUSE N40°W 25.2'
NE COR CONC BLK	3" MAPLE N65°E 12.2'	10" FRUIT TREE S20°W 65.84'
BAR FND S50°E 26.8'	12" SPRUCE S50°E 13.2'	6" MAPLE S45°W 76.28'
NW COR CONC BLK	SM COR SHED N07°E 18.2'	15" PEAR TREE S85°W 21.79'
BAR FND S02°W 14.9'	FD 1 1/4"	
11" B. CHERRY S75°W 82.95'	PIPE N02°12'W 12.43'	

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by Carl F. Roser 12028 Date 8-10-92