

SURVEY &
REMONUMENTATION

MAY 28 1997

LIBER 308 PAGE 692

LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

1061

For corners in Missaukee (County) Located In: Corner Code #

1. Public Land Survey	T <u>24N</u> R <u>6W</u>	<u>G-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

MISSAUKEE COUNTY MICHIGAN
RECORDED DEC 20 1996 *JAS LAM*
Roslyn Flare
REGISTER
Register of Deeds Stamp & File Number

I, J. Dean Geers, in a field survey on December, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		6		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- G-7) GLO Section post by Whelphley; Beech 15-S79W-24, Beech 12-N78W-47, Sugar 15-N67E-29
 - G-7) 1972 Ostling LCRC, Liber 1, Page 51; Found boat spike, pk. in PP-N63E-60.8, pk. in PP-N70W-90.9, pk. in 22" Maple-S42E-65.9
 - G-7) 1973 Radcliffe LCRC; Liber 1, Page 164; found 1/2" rod, TP-N80W-90.82, PP-S05W-43.51, TP-N75E-60.71
 - G-7) 1978 Granger Survey, Liber 5-3, Page 394; Found 1/2" rod, TP-N80W-90.82, PP-S05W-43.51, TP-N75E-60.71

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- G-7) Section corner common to Sections 15, 16, 21, 22, T24N, R6W. Found 1/2" Rebar of record; ±2' South of East-West centerline and in centerline of North-South Road. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- G-7) Set Missaukee County Mon. on existing Iron
 - S54E - 63.52 - 6" Birch
 - N38E - 69.81 - 4" White Pine
 - N40W - 64.53 - 12" Scotch Pine
 - S25W - 43.45 - Telephone Pole

Peer Group Reviewed and Approved
Date: 12-19-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers*
Surveyor's Michigan License No. 34977

