

MAY 28 1997

LIBER 308 PAGE 674

COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

# 1063

For corners in Missaukee (County) Located In: Corner Code #

1. Public Land Survey	T	<u>24N</u>	R	<u>6W</u>	<u>1-7</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Section	S		T		R
	S		T		R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

MISSAUKEE COUNTY MICHIGAN  
RECORDED DEC 20 1996 2:45 P.M.  
*Randy Klare*  
REGISTER  
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, J. Dean Geers, in a field survey on December, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- I-7) 1853 GLO Quarter Section post by Whelphley; Tam 13-N12W-33, Tam 20-N77 1/2 E-44, Cedar 6-S6 3/4 E-27
  - I-7) County Survey Notes: Survey in Section 14, corner was used
  - I-7) 1973 Radcliffe LCRC, Liber 1, Page 164; Set 5/8" pipe equal distance on line, TP-S45W-30.35, 5" Maple cluster - N10E-40.35, 8" Cedar-N40W-46.97
  - I-7) 1987 Myers Survey, Liber S-2, Page 358 and 394; Found corner of record

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- I-7) Section corner common to Sections 14, 15, 22 and 23, T24N, R6W. Found 5/8" Pipe of record in centerline East-West Road. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- I-7) Set 1/2" Iron with Miss. Co. Mon.  
N25W - 46.97' - 10" Cedar  
N20E - 40.22' - 5" Maple Clump  
S30E - 29.95' - Set Pk in Top 24" CMP  
N40E - 29.51' - Set Pk. in Top 24" CMP

Peer Group Reviewed and Approved  
Date: 12-19-96  
*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers*  
Surveyor's Michigan License No. 23977

