

SURVEY &
REMONUMENTATION

MAY 28 1997

LIBER 308 PAGE 696

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

1065

For corners in <u>Missaukee</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>24N</u> R <u>6W</u>	<u>K-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MISSAUKEE COUNTY MICHIGAN
RECORDED DEC 20 1996 JHS
A.M.
Carolyn Flare
REGISTER
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, J. Dean Geers, in a field survey on December, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


- A. Description of original monument and accessories and/or subsequent restoration:
- K-7) 1853 GLO section post by Whelphley; Sugar 13-S17E-22, Sugar 10-N14E-13, Beech 12-S59 1/4W-43
 - K-7) Corner used by County Surveyor in Survey of Section 14, No witnesses given.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- K-7) Section corner common to Sections 13, 14, 23 and 24, T24N, R6W. Found Old 1 1/2" Pipe in centerline intersection. This corner is accepted as the best available evidence of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- K-7) Set 1/2" Iron with Miss. Co. Mon.
S45E - 59.81' - Found Nail in 6" x 6" sign post
N40E - 66.10' - Found Nail 8" Red Pine
N15E - 39.06' - Southerly Northwest corner of concrete wing wall
S25W - 93.43' - Northeasterly most pylon for air strip

Peer Group Reviewed and Approved
Date: 12-19-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers*
Surveyor's Michigan License No. 33977



Date 12-19-96