

MAY 28 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1066

For corners in Missaukee (County) Located In: _____ Corner Code # _____

- | | | | | | | |
|--------------------------------------|---|------------|---|-----------|------------|-------|
| 1. Public Land Survey | T | <u>24N</u> | R | <u>6W</u> | <u>L-7</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

MISSAUKEE COUNTY MICHIGAN
RECORDED **DEC 20 1996** *J.D.G.*
J. Dean Geers
REGISTER
Register of Deeds Stamp & File Number

I, J. Dean Geers, in a field survey on December, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-7) 1853 GLO quarter post set by Whelpley; Beech 7-S39 3/4W-31, Sugar 8-N13 1/2E-21

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7) Quarter section corner common to Sections 13 and 24, T24N, R6W. Found "T" Iron @ centerline intersection. This corner is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7) Replaced "T" iron with 1/2 iron and Miss. Co. Mon.
S30E - 47.94 - Corner fence post
S30W - 79.67 - 4" Elm
N45W - 59.13' - Northeast corner of tel. riser
N55E - 70.27' - 14" Red Pine (Twin)

Peer Group Reviewed and Approved

Date: 12-19-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by _____ Date 12-19-96
Surveyor's Michigan License No. 33977

