

MAY 28 1997

LIBER 308 PAGE 698

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1067

For corners in Missaukee (County) Located In: _____ Corner Code # _____

1. Public Land Survey	T	<u>24N</u>	R	<u>6W</u>	<u>M-7</u>	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
2. Property Controlling In Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____
3. Miscellaneous Property In Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____

MISSAUKEE COUNTY MICHIGAN

RECORDED **DEC 20 1996** 9:45 A.M.

Carolyn Flare
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		18		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, J. Dean Geers, in a field survey on December, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-7) 1853 GLO found Section Corner Welpheg Beech - 18 - N81W-15, Sugar - 12 - S63W-39
- M-7) 1966 Young Survey; Found 1 1/2" pipe
- M-7) 1983 Wilcox Survey; Found 1 1/4" pipe 3' below surface in centerline of intersection. Raised with Iron and Cap, N58W-P.P.-58.60, N30W-12" Red Pine-66.85, N50E-P.P.- 42.84, S87E-P.P.- 44.32
- M-7) 1994 DNR LCRC, Liber 1, Page922; Found Wilcox Iron and Raised to surface with 1/2" Rerod, P.P.-N60W-58.64, 18" Red Pine - N30W - 66.93, Railroad tie corner fence post - East - 33'; Railroad tie corner fence post - S45W- 48.31

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-7) Section corner common to Sections 13 and 24, T24N, R6W and Sections 18 and 19, T24N, R5W. Found Iron with cap #14102 in centerline intersection. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-7) Set Missaukee County mon. on 1/2" Iron
N55W - 58.67' - P.P.
N55E - 42.90' - P.P.
S85E - 44.12' - P.P. Anchor
S50W - 48.38' - Corner fence post

Peer Group Reviewed and Approved

Date: 12-19-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by _____
Surveyor's Michigan License No. 3497

Date 12-19-96

