

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD


T. 24 N.R. 7 W.  
T. 25 N.R. 7 W. MISSAUKEE  
KALKASKA COUNTY

DESCRIPTION OF CORNER SECTION CORNER COMMON TO SECTIONS 1 - 2 - 35 - 36

CORNER MONUMENT SET 1" PIPE WITH 4" ALUMINUM CAP

DATE MONUMENT PLACED AND WITNESSED MAY 11, 1965

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

8" R. OAK S 68 W 71.3

7" MAPLE N 38 W 79.4

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

THIS CORNER WAS FOUND WHILE MAKING A SURVEY ON THIS TOWNSHIP LINE. FOUND 3/4" PIPE IN PLACE WHICH I CONCLUDE WAS ESTABLISHED BY FARGO ENGINEERING FOR CONSUMERS POWER COMPANY, PROBABLY IN LATE 1900'S. BENT-OVER PIPE AND BROKEN CROCKERY IDENTIFY IT AS FARGO. SITE FOR AT LEAST ONE POSSIBLE O.B.T. IN PLACE. CHECKS EXACTLY WITH STREAM CROSSING EAST. AN L.E.S. POST IS ABOUT FOUR CHAINS NORTH, BUT MUST BE DISREGARDED AS THESE POSTS WERE NOT INTENDED TO PROPERLY MARK THE CORNER.

CHECKS OKAY FOR BEARING OF TOWNSHIP LINE.

SURVEYOR'S SEAL

SIGNED Kenneth Ostling DATE MAY 26, 1965  
REGISTERED LAND SURVEYOR 10068