

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD


T. 24 N.R. 7W
T. 24 N.R. 8W
Missaukee COUNTY

DESCRIPTION OF CORNER Sec. corner common to Sections 7-18-12-13

CORNER MONUMENT Set 1" pipe with 1/4" Aluminum cap

DATE MONUMENT PLACED AND WITNESSED April 29, 1966

WITNESSES TO CORNER.....



10" Twin R. Oak N 54 W 50.0'

8" R. Oak S 6 W 29.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this township.
Found 3/4" pipe with concrete cylinder at corner as established in early
survey by County Surveyor. Fits occupation, old fence lines E-W and N,
but USBTs all gone. Buried previous monument with our corner.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostberg* DATE April 5, 1966
REGISTERED LAND SURVEYOR #10068