

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 N. R. 7 W


Missaukee COUNTY

DESCRIPTION OF CORNER 1/4 corner common to sections 5-6

CORNER MONUMENT Set 1" pipe with 4" Aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 23, 1966

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

7" R. Pine S 86 E 8.4'

12" B. Oak S 61 W 74.5'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement between section corners. Unable to identify USBTs but this point is faced by one stump which has what appears to be evidence of an N.B.T., probably the result of early county surveyor survey.

SURVEYOR'S SEAL

SIGNED *Ronald J. Ostling* DATE June 24, 1966
REGISTERED LAND SURVEYOR #10068