

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 24 N. R. 7 W. ●	J-9; J-11; K-9; K-10
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 6, 1979, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A - Description of original monument and accessories and for subsequent restoration.~~
C. (continued)

K-10
Fd. 1/2" rod w/RLS cap; replaced w/DNR Mon. & ced. post
*4" Maple S40°W 32.59
*4" Maple Due S 31.30
*6" Maple S80°W 39.47
*8" Cherry N60°W 19.35
*RLS J. Wilcox witnesses

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- J-9** Fd. J. Cavanagh 1909 round conc. mon. with 1 1/4" pipe in same and remains of his hemlock witness, N25 1/2°E, 6.6'.
- J-11** Fd. conc. mon. in E-W trail road, per J. G. Cavanagh 1909 survey & remains of one poss. witness (hem. 30°S12 1/2°E, 88.4'). Old corner fence post with fn. to N & W is 15'± N & 18'± W of fd. monument.
- K-9** Fd. 1 1/4" pipe in conc. (Cavanagh 1909 mon.) per J. L. Wilcox certificate surveys in Sec. 24 & 25. A new trail road is 45'± East.
- K-10** Fd. 1/2" rod per J. L. Wilcox certificate survey in Sec. 25, said 1/2" rod being established equidistant & on line between section corners 1/2 mile N & 1/2 mile S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9	J-11	K-9
Fd. J. CAV. mon. & set cedar post w/loc. tag	Fd. 1 1/2" pipe in concrete	Fd. 1 1/4" pipe in conc. & set cedar post w/loc. tag
5" Maple N60°E 13.7	5" Maple S10°W 76.9	*15" Maple S80°W 9.55
8" Maple S65°E 23.7	10" Cherry S65°W 72.6	*8" Maple Clstr. S43°E 41.56
3" Maple N15°W 4.0	Ctr. large rock 1 1/2' x 2 1/2' N15°W 59.9	*8" Maple S80°E 32.65
Old E-W fence Due S 68'±	Set ced. post w/loc. tag Due N 33'	*15" Maple N08°W 42.96
Curved E-W trail Due S 45'±	Ctr. of E-W drivable trail Due S 2'±	*RLS J. Wilcox witnesses
		E-W fence Due N 30'±

SIGNED BY Carl F. Roser DATE 02/17/80

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:


SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

MISSAUKEE COUNTY
PIONEER TOWNSHIP