

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 24 N. R. 7 W.	C-9; C-10; C-11; D-11
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 30, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A - Description of original monument and accessories and/or subsequent restoration:

C. (continued)

D-11

Fd. 1 1/4" pipe in round conc. base;
added cedar post w/loc. tag

12" Twin Basswood	N15°E	6.94
14" Maple	S75°E	16.48
7" Twin Maple	S10°E	13.14
5" Maple	N70°W	9.82

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-9** Found concrete monument per J. G. Cavanagh 1909 survey.
- C-10** Fd. iron as set by RLS H. Fluharty (corner set S.P. to fd. sec. corners 1/2 mile N and 1/2 mile S). Center E-W trail is 27'± south.
- C-11** Found concrete monument per J. G. Cavanagh 1909 survey.
- D-11** Fd. & accepted pipe in concrete per J. G. Cavanagh 1909 survey; fd. one Cavanagh witness (40" W. Pine N39-3/4°E, 39.3') remains.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9	C-10	C-11
Fd. 1" pipe in conc. in mon. box	Fd. 5/8" rerod w/plastic RLS cap	Fd. 1 1/4" pipe in conc. &
14" Twin W. Birch S75°W 146.15	#18223 & set ced. post w/loc. tag	set ced. post w/loc. tag
6" Maple S25°E 51.55	8" Twin Cherry N64°W 55.67	9" Ash N59°E 10.05
12" Maple S65°E 96.24	18" Maple N12°E 26.75	14" Ash N05°W 37.00
Ctr. E-W B' top rd. Due N 5.2'	12" Maple N82°E 7.78	5" Maple S73°W 4.59
Set cedar post w/loc. tag	13" Maple Due W 6.03	5" Maple S49°E 13.83
Due S 33'	Fd. rerod w/RLS. Cap #18223 S05°W 30.79	Ctr. N-S trail Due E 58'±

SIGNED BY Carl F. Roser 5-13-81 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

MISSAUKEE COUNTY
PIONEER TOWNSHIP