

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 24 N. R. 7 W.	D-9; E-10; E-11; F-11
2. PROPERTY CONTROLLING IN SECTION.....	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. S. R. E. W.	
4. LOT NO., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 4, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~=====~~ *(Note: This line is crossed out in the original document)*

C. (continued)

F-11
 Fd. 1" pipe in concrete &
 set cedar post w/loc. tag
 9" Maple N45°E 30.5
 8" Maple S80°E 38.8
 8" Ironwood S65°W 39.1

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- D-9** Fd. iron as set by RLS H. Fluharty (cor, set S.P. between section corners ½ mile E and ½ mile W.)
 - E-10** Fd. pipe in concrete per J. G. Cavanagh 1909 survey. Old N-S fence is 31'± east.
 - E-11** Fd. pipe in concrete per J. G. Cavanagh 1909 survey.
 - F-11** Fd. concrete mon. (added several large rocks) per J. G. Cavanagh 1909 survey.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9	E-10	E-11
Fd. 5/8" rerod w/RLS cap MEI #18223	Fd. 1 1/4" pipe in conc. base; added ced. post w/loc. tag	Fd. 1 1/4" pipe in round conc. base; added cedar post w/loc. tag
9" Maple S40°E 52.52	12" Cherry S51°W 10.23	15" Twin Maple S55°E 12.70
10" Maple S37°W 35.75	11" Cherry N64°W 25.74	10" Maple N60°W 13.48
12" Maple N44°W 53.91	13" Rock Elm N39°W 4.76	7" Maple N41°E 6.94
Fd. 5/8" rerod w/RLS cap #18223 S02°W 28.91		
Set ced. post w/loc. tag Due S 33'		

E-W B' top rd. Due N 4.1'±
 SIGNED BY _____

Carl F. Roser

DATE 5-13-81



SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

MISSAUKEE COUNTY
 PIONEER TOWNSHIP