

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 24 N. R. 7 W.	F-9; G-9; G-10; G-11
2. PROPERTY CONTROLLING IN SECTION.....	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. S. R. E. W.	
4. LOT NO., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 30, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A - Description of original monument and accessories and for subsequent restoration:

C. (continued)

G-11

Fd. 1" pipe in concrete & set cedar post w/loc. tag

7" Maple	N18°W	11.86
9" Maple	S88°W	22.90
11" Maple	S01°W	6.50

Ctr. of old N-S grade W 17'±
Ctr. N-S winding gravel road E 164'±

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- F-9** Fd. conc. mon. per J. G. Cavanagh 1909 survey. Corner is in old (mostly down) N-S fence, between two pine plantations. Corner fd. & accepted in RLS J. Wilcox 1978 survey.
- G-9** Fd. conc. mon. per J.G. Cavanagh 1909 survey, N-S ROW fences are 33' W & 27' E. Corner was fd. (buried) in N-S gravel road (has been hit by grader). There is a crooked fence E in trees with some posts, due S 27'±.
- G-10** Fd. conc. mon. per J.G. Cavanagh 1909 survey. Corner falls on E edge old N-S overgrown buggy trail road & 10'± E of old N-S fence.
- G-11** Found concrete monument per J. G. Cavanagh 1909 survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9	G-9	G-10
Found 1" pipe in concrete & set cedar post w/loc. tag	Fd. 1 1/4" pipe in conc. in appr. ctr. N-S gravel road	Fd. 1" pipe in conc. & set cedar post w/loc. tag
18" Maple S07°W 95.76	8" Maple S61°E 38.00	9" Maple S76°E 17.17
5" Maple N05°E 157.52	6" Twin W. Birch S14°E 69.15	8" Maple S30°E 3.73
	8" W. Pine N33°W 36.26	12" Maple S03°E 18.35
	Set cedar post w/loc. tag Due W 33'±	16" Maple N20°W 23.03

SIGNED BY Carl F. Roser 5-13-81 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ MISSAUKEE COUNTY
PIONEER TOWNSHIP

