

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 24 N. R. 7 W.	E-9
2. PROPERTY CONTROLLING IN SECTION 29	T. 24 N. R. 7 W.	7; 10
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 30, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-9** PK Nail in E. bound lane of old M-66 b'top road as used by RLS J. Wilcox & RLS H. L. Fluharty for NE corner Sec. 29. Corner is in line w/fence remains (down) to S. & with avg. center of old road to N. MSHD ROW sheet in this area of Old M-66 is very ambiguous, indicating that the sec. line between Sec. 20 & 29 may be over 33' S of the center of M-66 (line on ROW sheet - cor. not dimensioned). The NW cor. of Sec. 29 (mon. box) is 5' S of center of M-66; a lat. of this cor. by single proportion for 1/2 mile to N & S would be approx. 6' N. We therefore accepted and replaced the PK nail with a 3/4"x18' solid iron rod.
- 7** Fd. & accepted 1/8 corner as set by RLS H. Fluharty.
- 10** Fd. & accepted 1/8 corner as set by RLS H. Fluharty.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9	7	10
Drove 3/4"x18" solid iron rod in place of P.K.	Fd. 5/8" rerod w/RLS Cap #18223 & set ced.post w/loc. tag.	Fd. 5/8" rerod w/plastic cap #18223; added ced.post w/loc. tag.
3" R. Pine N34°E 53.64	13" Cherry N87°E 23.00	7" Maple S62°W 5.44
20" Oak S55°E 68.54	3" Maple S64°E 61.99	8" Maple N34°E 20.62
17" Beech S05°W 36.27	16" Twin Maple S33°E 31.10	8" Maple N10°W 19.27
Ctr. E-W b'top rd. Due N 7'		4" Maple S45°E 1.16
Set ced. post w/loc. tag Due S 26'±		

SIGNED BY Carl F. Roser 5-13-81 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ MISSAUKEE COUNTY PIONEER TOWNSHIP