

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MISSAUKEE

(County)

Located In:

Corner Code \neq

1. Public Land Survey

T 24N R 7W

A-3, A-4,

T _____ R _____

A-5

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S 7

T _____ R _____

10

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, C.F. ROSER, in a field survey on OCT. 10, 1992, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-3

A-4

A-5

10

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-3

A-4

A-5

10

FD DEPT MON FOR NW COR OF SEC 7. DEPT MON WAS RESTORED FROM REMAINS OF 1909 HEMLOCK NBT STUMP (AS NOTED IN 1909 COUNTY SURVEYOR J.G. CAVANAGH NOTES) BY LS, K.OSTLING IN 1966 DEPT SURVEY. ALSO FD LARGE ROCK ON W. SIDE OF MON.

FD DNR MON. ALONG SIDE OF CONC MON FOR W1/4 COR SEC 7. FITS WITS PER J.WILCOX 1974 CERT OF SURVEY. B/WIRE FN REMAINS TO EAST (ON GROUND) & FN REMAINS SOUTH ARE 17' EAST.

FD DEPT MON AS SET BY LS, K.OSTLING IN 1966 DEPT SURVEY. KJO FD PIPE IN CONC HERE AS ESTABLISHED BY EARLY CO SURVEYOR. COR FITS FNS E-N & N PER KJO IN 1966, FN'S MOSTLY DOWN MON, WIRE IN TREES ON GROUND AND A FEW POST TO EAST.

ESTABLISHED NW COR OF FRL S1/2 OF FRL SW1/4 OF SEC 7 PER STANDARD BLM INSTRUCTIONS. OLD N-S B/WIRE FN REMAINS, ON GROUND, ARE 5'± EAST AND OLD FN REMAINS EAST ARE 20'± N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FD DEPT MON & CEDAR POST.

13" MAPLE	N16°W	14.0'
14" MAPLE	S84°E	15.3'
8" MAPLE	S10°W	23.2'
6" MAPLE	S80°W	28.4'

FD DNR MON AND CEDAR POST.

16" S. MAPLE	N20°W	14.78'
4" S. MAPLE	N70°E	8.42'
16" TW. BEECH	S45°E	4.55'
16" S. MAPLE (CLP)	S85°W	39.43'

FD DEPT MON AND CEDAR POST.

16" R. OAK	N55°W	49.7'
5" MAPLE	N34°E	7.7'
9" MAPLE	S84°E	19.1'
14" R. OAK	S05°W	29.1'

DROVE 5/8" x 3/4" REROD W/LS CAP & SET CEDAR POST W/LOC TAG.

4" S. MAPLE	N55°E	15.3'
8" BEECH	S65°E	31.1'
5" S. MAPLE	S75°W	19.2'
21" R. OAK	N40°W	13.2'

1= K.J.OSTLING 1966 WIT.

2= P.S. J.WILCOX 1974 WIT.

3= KJO WIT.

Signed by Carl F. Roser 4-27-94

Date

Surveyor's Michigan License No. 12028

