

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>29</u> T <u>24N</u> R <u>7W</u>	<u>10</u>
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on Feb. 19, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 10 - Rec. Sur. L. S-1, P. 460-471 - Set 5/8" x 18" Iron w/RLS Cap - H. Flaharty - 1978
 Rec. Sur. L. S-2 P. 514-515 - Set 5/8" x 18" Iron w/RLS Cap - H. Flaharty - 1989
 LCRC - L. 1, P. 621 -FND 5/8" x 18" rered w/cap 18223 - C. Roser - 1981
 7" Maple S62° W 5.44'
 8" Maple N34° E 20.62'
 8" Maple N10° W 19.27'
 4" Maple S45° E 1.16'



* Above wits. agree w/L. S-1. P. 460-471 - Wit.

LCRC - L.1P, 819 - Set 5/8" Iron w/cap at Department of Natural Resources Post

4" Maple N45°W 6.62; 10" Maple N15°E 23.33; 12" Maple N75°E 6.42'; 18" DBL. Maple S60°W 16.34'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 10 - S 1/16 Cor. between Sec. 29 & 30 - FND 5/8" rered w/PS cap in 2 1/2" x 2 1/2" galv. angle iron fence Post and Department of Natural Resources Cedar Guard Post. Monument agrees with LCRC L. 1, P. 819 & Rec. Sur L. S-2, P. 514 - 515 and is a proper BLM procedure position.

Ref. Pt. "B" - Position as noted in Rec. Sur. L. S-1, P. 460-471 & LCRC L. 1, P. 621. Position was established 1/2 way and on line between C-11 and S.P. Position @ C-10 - (S.P. Position found to be in error). No Iron was found here - apparently removed by H. Flaharty. Monument position established using improper procedures and is not utilized as Cor. #10 in this survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 10 - Monument as noted in Part "B"
 N48°W 6.61' to Set Nail in SW Side 4" S. Maple (HF)
 S56°W 16.33' to Set Nail in SE Side 11" Tw. S. Maple (HF)
 N68°E 6.42' to Set Nail in NW Side 11" S. Maple (HF)
 N10°E 23.10' to Set Nail in W Side 9" S. Maple
Reference Pt 'B' - 4.17 N & 6.13'W - No Iron

Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 9/10/1997