

SURVEY R
MICHIGAN

#1018

JAN 30 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Missaukee COMMISSION
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 24 R 7 A-7
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

MISSAUKFF COUNTY MICHIGAN

RECORDED JAN 2 1996 1:15 P

Paulyn Flare
REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Daniel E. Schripsema in a field survey on August, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-7) 1838 GLO post by John Brink, Deputy Surveyor
- A-7) 1967 MDOT/Wilcox Gov't Monument Witness Recordation, Liber-page 298: Found 1" pipe in conc.
- A-7) MDOT Control Section SS57013, Job #04474A, sheet #5: Found 1" pipe in conc.
- A-7) 1979 Wilcox LCRC, Liber-page 577: Found 1" Iron pipe
- A-7) 1979 Wilcox survey, Liber S-1, page 525: Found 1" Iron in conc.
- A-7) 1980 Wilcox survey, Liber S-2, page 49: Found 1" pipe
- A-7) 1981 Roser survey, Liber-page 625: Found conc. mon.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-7) Section corner common to Sections 19 and 18
- Found 1" Iron rod in centerline Rd. North and South, 1.75' South of centerline Rd. East, approx. .75' deep. This corner is accepted as a careful and faithful perpetuation of the location of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-7) Placed Mon. Box and Brass Missaukee County Monument on existing corner with #24617

*S49°W 53.67 10" Tamarack
 *N43°W 75.50 12" Cherry
 N68°W 45.83 11" Red Pine
 N81°E 108.22 P.Pole

* = Fd. witness nail

Peer Group Reviewed and Approved

Date: 1-2-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed Daniel E. Schripsema Date 12-29-95
Surveyor's Michigan License No. 24617

