

JAN 30 1996

#1039

LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Missaukee
(County)

Located in:

Corner Code #

MISSAUKIE COUNTY MICHIGAN

RECORDED JAN 2 1996 1:15 P
J. Dean Geers
REGISTER

- 1. Public Land Survey T 24 R 7 A-8
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Section S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel E. Schripsema, in a field survey on August, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-8) 1838 GLO post by John Brink, Deputy Surveyor
- A-8) 1967 MDOT/Wilcox Gov't Monument Witness Recordation: Set 1" pipe
- A-8) MDOT Control Section SS57013, Job #04474A, sheet #5: Found 1" pipe
- A-8) 1980 Wilcox survey, Liber S-2, page 49: Found 1" pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-8) West 1/4 corner common to Section 19

Found 5/8" Iron in centerline Rd. North & South opposite fence line East. This corner is accepted as a careful and faithful reestablishment of the location of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-8) Placed Mon. Box and Brass Missaukee County Monument on existing corner with #24617
 - *S83°E 29.90 Fence Post
 - *S45°E 33.69 P.Pole
 - N22°E 101.01 P.Pole
 - N66°W 55.62 5" Scotch Pine
- * = fd. witness nail

Peer Group Reviewed and Approved
Date: 1-2-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by: [Signature]
Surveyor's Michigan License No. 24617

Date 12-29-95