

**SURVEY &  
REMONUMENTATION**

#937

DEC 07 1994

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 290 PAGE 14

For corners in **COMMISSION**

Missaukee  
(County)

Located In:

Corner Code ##

- |                                    |   |            |   |           |            |
|------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey              | T | <u>24N</u> | R | <u>7W</u> | <u>A-9</u> |
|                                    | T | _____      | R | _____     | _____      |
|                                    | T | _____      | R | _____     | _____      |
|                                    | T | _____      | R | _____     | _____      |
| 2. Property Controlling in Section | S | _____      | T | _____     | _____      |
|                                    | S | _____      | T | _____     | _____      |
| 3. Miscellaneous Property in Sec.  | S | _____      | T | _____     | _____      |
|                                    | S | _____      | T | _____     | _____      |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

MISSAUKEE COUNTY MICHIGAN  
RECORDED **OCT 28 1994** <sup>1:15</sup> P.M.

*Paulyn Flare*  
REGISTER

Register of Deeds Stamp & File Number

I, J. Dean Geers, in a field survey on July 24, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- A-9) 1838 GLO Section post by John Brink, Deputy Surveyor  
Beech 15 S 31 1/2 W 12, Sugar 9 N 31 1/2 W 15
- A-9) 1987 County Surveyor Notes: Corner was used but no witnesses given
- A-9) 1909 Cavanagh, County Surveyor: Gas pipe in concrete  
Apple 6 N 41 1/2 W 83 1/2, Poplar 2 S 41 1/2 E 46
- A-9) 1967 MDOT, Liber 1, page 304: Found 3/4" bolt in intersection
- A-9) 1980 Wilcox, S-2, page 49, S-2, page 54: Found 3/4" bolt recorded in Liber 1, page 304

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-9) Section corner common to Sections 19, 30, T24N, R7W, Section 24, 25, T24N, R8W  
Found 3/4" Bolt over 1" Pipe as recorded in Liber 1, page 304. This corner is accepted as a careful and faithful perpetuation of the original corner. Corner is in the Centerline intersection of North-South and East-West roads.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-9) Replaced Bolt with 1/2" Iron and Missaukee County monument in monument box

- S 25 W - 76.27 - 12" Apple
- S 63 W - 54.87 - Post at back of telephone riser
- N 31 W - 73.58 - 40" Poplar
- N 83 E - 119.29 - 24" Maple

Peer Group Reviewed and Approved

Date: 10-26-94  
*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative



Date 9/28/94

Signed by \_\_\_\_\_  
Surveyor's Michigan License No. 33977