

DEC 07 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 290 PAGE 13

For corners in

<u>Missaukee</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>24N</u> R <u>7W</u>	<u>A-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

MISSAUKEE COUNTY MICHIGAN

RECORDED OCT 28 1994 ¹¹⁵ p.m.

Carolyn Flare
REGISTER

Register of Deeds Stamp & File Number

I, J. Dean Geers in a field survey on July 24 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-10) 1838 GLO Quarter Section post by John Brink, Deputy Surveyor
Beech 10 S 48 W 28, Beech 11 N 14 W 22
- A-10) 1897 County Surveyor Notes: Corner was used but no witnesses given
- A-10) 1909 Cavanagh, County Surveyor: Gas pipe in concrete
Corner fence post S 87 E 40, Poplar 12 N 21 1/2 E 128
- A-10) 1967 MDOT, Liber 1, page 301: Found 1 1/2" pipe in concrete monument 15" below surface.
Raised surface with 1/2" pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-10) Quarter corner common to Sections 30, T24N, R7W and 25, T24N, R8W

Found 1/2" Pipe in centerline of North-South road. This corner is accepted as a careful and faithful perpetuation of the position of the original corner. Corner is in the Centerline of North-South road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


A-10) Set Iron and Missaukee County monument in monument box

- West - 42.58 - Iron
- N 56 W - 40.00 - 4 x 4 post @ telephone riser
- S 50 E - 39.15 - Twin 8" Red Pine
- S 22 E - 72.07 - Twin 8" Red Pine

Peer Group Reviewed and Approved

Date: 10-26-94

J. Dean Geers
J. Dean Geers, Missaukee Co. Representative



Signed by *J. Dean Geers*
Surveyor's Michigan License No. 33977

Date 9/28/94