

DEC 07 1994

LIBER 290 PAGE 12

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

Form with fields for Missaukee (County), Located In: T 24N R 7W, Corner Code #7: A-11, and numbered sections 1-5 for survey details.

MISSAUKEE COUNTY MICHIGAN

RECORDED OCT 28 1994 1:15 P.M.

Signature of Evelyn Flare, REGISTER

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13, containing numbers 1-36.

I, J. Dean Geers, in a field survey on July 24, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-11) 1838 GLO Section post by John Brink, Deputy Surveyor Sugar 7 S 60 1/2 W 22, Sugar 28 N 20 W 22
A-11) 1909 Cavanagh, County Surveyor: Gas pipe in concrete Gate post S 87 1/2 E 43, Corner post S 89 W 34
A-11) 1967 MDOT: Liber 1, page 306, Found boatspike 6" below surface

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-11) Section corner common to Sections 30, 31, T 24N, R7W, Sections 25, 36, T24N, R8W

Found 5/8" Iron in monument box. This corner is accepted as a careful and faithful perpetuation of the position of the original corner. Corner is +/- 29.5' West of North-South road Centerline.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11) Found 5/8" Iron and added Missaukee County monument in monument box

- S 79 E - 90.18 - Power Pole
West - 81.90 - Power Pole
S 42 W - 79.26 - Northeast corner of church
N 60 E - 80.67 - 12" Maple

Peer Group Reviewed and Approved

Date: 10-26-94
J. Dean Geers, Missaukee Co. Representative



Signed by [Signature]
Surveyor's Michigan License No. 33977

Date 9/28/94