

JAN 30 1996

#1040

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Missaukee COMMISSION (County)

Located In:

Corner Code #

MISSAUKEE COUNTY REGISTER

RECORDED JAN 2 1996 115 P

Charles K. ... REGISTER

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 24 R 7 A-12
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Section S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Daniel E. Schripsema, in a field survey on August, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors, or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
 - A-12) 1838 GLO post by John Brink, Deputy Surveyor Sugar 11
 - A-12) 1967 MDOT/Wilcox Government Monument Witness Recordation: Set 1/2" Iron from Highway wits.
 - A-12) 1971 MDOT Control Sec. SS57013, sheet #5: Found 1/2" rod
 - A-12) 1973 Erickson survey, Liber S-1, page 117-119: Found 1/2" rod
 - A-12) 1973 MDOT/Slaminski Government Monument Witness Recordation: Reset from witnesses 3/4" Pipe & Cap, Set Mon. Box 3" below ground surface in old road bed.
 - A-12) 1977 Wilcox LCRC, Liber-page 307: Set 1/2" rod from witnesses in old Hwy. survey
 - A-12) 1989 Schripsema survey, Liber S-2, page 567: Found 1/2" Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 A-12) West 1/4 corner common to Section 31

 Found 1/2" Iron Bar in Mon. Box 2.5' South of the centerline Rd. West and 194' East of centerline M-66. 50' East of North & South fenceline. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 - A-12) Replaced existing corner with 1/2" Iron and brass cap with #24617
 - *S74°W 106.47 P.Pole
 - N34°W 175.79 P.Pole
 - *S83°E 50.03 Fence Post
 - *N51°E 72.09 Fence Post
- * = fd. witness nail

Peer Group Reviewed and Approved

Date: 1-2-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *Daniel E. Schripsema* Date 12-29-95
Surveyor's Michigan License No. 24617