

SURVEY & REMONUMENTATION

#939

DEC 07 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 290 PAGE 16

For corners in **COMMISSION**

<u>Missaukee</u> <small>(County)</small>	Located In:	Corner Code #:
1. Public Land Survey	T <u>24N</u> R <u>7W</u>	<u>C-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

MISSAUKEE COUNTY MICHIGAN

RECORDED **OCT 28 1994** 1:15 P.M.

Carolyn Klare
REGISTER

Register of Deeds Stamp & File Number

I, J. Dean Geers, in a field survey on July 24, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-9) 1852 GLO Section post by Whelpley, Deputy Surveyor
Sugar 26 N 37 W 20, Beech 8 S 53 E 11, Sugar 10 S 45 3/4 W 31
- C-9) 1909 Cavanaugh, County Surveyor: Gas pipe in concrete
Sugar 10 S 58 W 133, Elm 3 S 15 1/2 E 17 1/2, Stake N 40 1/4 E 47 1/2
- C-9) 1967 MDOT: Found concrete monument in monument box
- C-9) 1978 Mears Engineering: S-1, page 460, Found 1" pipe in concrete in monument box
- C-9) 1981 Roser: Liber 1, page 629, Found 1" pipe in concrete in monument box per 1909 Cavanagh survey
- C-9) 1983 Wilcox: S-2, page 168, Found 1" pipe in concrete in monument box
- C-9) 1990 Fluharty: Liber 1, page 819, Found 1" pipe in concrete monument box per 1909 Cavanagh survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-9) Section corner common to Sections 20, 29, 19 and 30

Found 1" pipe in concrete in monument box per 1909 Cavanagh survey. This corner is accepted as a careful and faithful perpetuation of the position of the original corner. Corner is ±5.5' South of East-West road Centerline.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-9) Found 3/4" pipe and raised with 1/2" Iron and Missaukee County monument in monument box

- S 06 W - 32.99 - DNR Post
- S 34 E - 48.30 - 5" Iron wood
- N 08 W - 45.28 - 6" Poplar
- N 75 E - 95.03 - 8" Jack Pine

Peer Group Reviewed and Approved

Date: 10-26-94
J. Dean Geers
 J. Dean Geers, Missaukee Co. Representative



Signed by *J. Dean Geers* Date 9/28/94

Surveyor's Michigan License No. 33977