

SURVEY & REMONUMENTATION

JAN 16 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Missaukee

(County)

Located in:

Corner Code #

1. Public Land Survey

T24NR 7W

C-13

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

J. Dean Geers in a field survey on June, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

#1168
LIBER 314 PAGE 1249
MISSAUKEE COUNTY MICHIGAN
RECORDED NOV 10 1997 4:30 P.M.
Carolyn Flare
REGISTER
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- C-13) 1838 GLO Section Post by John Brink, Deputy Surveyor; Beech 14-N58W-38, Maple 12-N65E-30
- C-13) 1909 Cavanagh County Surveyor; Set Gas Pipe in concrete, Twin Sugar-S12E-17½, Sugar 18-N49E-23
- C-13) 1973 Erickson-Wilcox LCRC, Liber 1, Page 148; Set 1/2" Rod in centerline of gravel road at proportionate distance along Township line; S20E-37.97-12" Maple, N45W-51.26-16" Maple, N20W-39.20-12" Maple in clump
- C-13) 1981 DNR LCRC, Liber 1, Page 623; Found Rerod set by Erickson-Wilcox; N45W-51.29-11" Maple, N15W-39.18-16" Maple, S17E-37.97-12" Maple, North-33-Cedar Post
- C-13) 1988 Wilcox Survey, Liber S-2, Page 567; Found 1/2" Rerod as recorded.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-13) Section Corner common to Sections 31 and 32, T24N, R7W and Sections 6 and 5, T23N, R7W; Found 1/2" Iron and Cap as recorded in Liber 1, Page 148 in centerline of East-West Road. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-13) Set Missaukee County Monument on existing 1/2" Iron
 - N06E 32.95 Found Iron
 - N17W 39.19 Tri 12" Maple - Found Nail
 - N40W 51.30 20" Maple - Found Nail
 - S15E 37.99 14" Maple

Peer Group Reviewed and Approved
Date: 10-15-97
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers*
Surveyor's Michigan License No. 33977



Date 10-22-97