

**SURVEY &
REMONUMENTATION**

940

DEC 07 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 290 PAGE 17

For corners in **COMMISSION**

Missaukee <small>(County)</small>	Located In:	Corner Code -#
1. Public Land Survey	T <u>24N</u> R <u>7W</u>	<u>D-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MISSAUKEE COUNTY MICHIGAN

RECORDED **OCT 28 1994** 1/15 PM

Caryn Flare
REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, J. Dean Geers, in a field survey on July 24, 1994, do hereby certify that under requirements of P A 74, Michigan P A of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-9) 1852 GLO Quarter Section post by Whelpley, Deputy Surveyor
Hemlock 20 S 9 1/2 E 22, elm 26 N 72 W 23
- D-9) 1909 Cavanaugh, County Surveyor: Gas pipe in concrete
Sugar 16 S 16 3/4 W 61, Hemlock 30 S 60 3/4 E 132
- D-9) 1978 Mears Engineering, S-1, page 460: Set corner single proportion between section corners
- D-9) 1981 Roser, Liber 1, page 628: Found Iron as set by Flaherty and recorded at S-1, page 460


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-9) Quarter corner common to Sections 20 and 29
Found 1/2" Iron as recorded in Liber 1, page 628. This corner is accepted as a careful and faithful re-establishment of the position of the original corner. Corner is ±3.5' South of East-West road Centerline.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-9) Set 1/2" Iron and Missaukee County monument in monument box
S 10 E - 38.06 - 6" Maple
S 40 E - 52.64 - 10" Maple
N 18 W - 45.64 - 12" Maple
N 35 W - 51.77 - Post @ telephone riser
South - 33.00 - DNR Post

Peer Group Reviewed and Approved
Date: 10-26-94
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative



Signed by *J. Dean Geers* Date 9/28/94

Surveyor's Michigan License No. 33977