

SURVEY & REMONUMENTATION

JAN 16 1998

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corner SECTION

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T24NR 7W	D-13
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

1169
LIBER 314 PAGE 1250
MISSAUKEE COUNTY MICHIGAN
RECORDED NOV 10 1997 4:30 P.M.
Caryn Flare
REGISTER
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, J. Dean Geers, in a field survey on June, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-13) 1838 GLO Quarter Section Post by John Brink, Deputy Surveyor; Sugar 8-N73W-30, Beech 10-N16E-24
- D-13) 1909 Cavanagh County Surveyor; Set Gas Pipe in concrete, Beech 8-N10½E-28, Sugar 14-N39½W-41
- D-13) 1973 Erickson-Wilcox LCRC, Liber 1, Page 149; Set 1/2" Iron at proportionate distance along Township line 4' North of centerline gravel road, N35W-43.28-18" Oak, S05W-37.02-5" Maple, N40E-43.59-4" Maple
- D-13) 1981 DNR LCRC, Liber 1, Page 623; Found and accepted Iron as set by Erickson-Wilcox; N35W-42.85-21" Twin Oak, S10W-37.08-7" Maple, N50E-43.59-6" Maple, North-33-Cedar Post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


- D-13) Quarter Corner common to Section 32, T24N, R7W and Section 5, T23N, R7W; Found Iron as recorded in Liber 1, Page 149, ±3' North of centerline of East-West road. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-13) Set Missaukee County Monument on existing 1/2" Iron
S06W 37.19 8" Maple, Found Nail
N05E 33.39 DNR Post, Found Nail
N51E 43.92 6" Maple, Found Nail
N30W 42.76 20" Oak, Found Nail

Peer Group Reviewed and Approved
Date: 10-15-97
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers*
Surveyor's Michigan License No. 33977



Date 10-22-97