

SURVEY & REMONUMENTATION

JAN 16 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1170

LIBER 314 PAGE 1251

SECTION

For corners in

Missaukee
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------------------------|-------------|
| 1. Public Land Survey | T <u>24</u> N R <u>7</u> W | <u>E-13</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

MISSAUKEE COUNTY MICHIGAN

RECORDED NOV 10 1997 4:30 PM

Paulyn Klare
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, J. Dean Geers, in a field survey on June, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- E-13) 1838 GLO Section Post by John Brink, Deputy Surveyor; Beech 14-N68W-25, Beech 13-N34E-29
- E-13) 1909 Cavanagh County Surveyor; Set Gas Pipe in concrete, Sugar 22-N15W-35, Beech 24-S28E-22
- E-13) 1973 Erickson-Wilcox LCRC, Liber 1, Page 153; Set 1/2" Iron in centerline gravel road by proportionate distance along Township line N30E-43.73-5" Maple, N30W-42.58-6" Maple, S25W-43.67-8" Maple
- E-13) 1981 DNR LCRC, Liber 1, Page 623; Found and accepted Iron set by Erickson-Wilcox; S38W-43.65-9" Maple, N38E-43.76-7" Maple, N31W-42.62-7" Maple, North-33-Cedar Post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E-13) Section Corner common to Sections 32 and 33, T24N, R7W and Sections 4 and 5, T23N, R7W; Found Iron as recorded per Liber 1, Page 623. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-13) Set Missaukee County Monument on existing Iron
 - N28W 42.41 8" Maple
 - N38E 43.83 10" Maple
 - S37W 43.69 12" Maple
 - S27E 51.16 8" Maple


Peer Group Reviewed and Approved

Date: 10-15-97

J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by _____

Surveyor's Michigan License No. 33977



Date 10-22-97