

# SURVEY & REMONUMENTATION

**JAN 16 1998**

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

# 1171

For corners in **SECTION**

<u>Missaukee</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>24</u> N R <u>7</u> W	F-13	
	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____	_____
	S ___ T ___ R ___	_____	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	_____
	S ___ T ___ R ___	_____	_____

LIBER 314 PAGE 1252

MISSAUKEE COUNTY MICHIGAN

RECORDED NOV 10 1997 4:30 PM

*Paulyn Flare*  
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, J. Dean Geers, in a field survey on June, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- F-13) 1838 GLO Quarter Section Post by John Brink, Deputy Surveyor; Sugar 12 was Quarter Section Corner
- F-13) 1909 Cavanagh County Surveyor; Set Gas Pipe in concrete, Hemlock 20-N64E-47½, Sugar 30-S17E-65
- F-13) 1973 Erickson-Wilcox LCRC, Liber 1, Page 150; Set 1/2" Iron 6' North of centerline of gravel road at proportionate distance along Township line N40E-46.23-11" Maple, N05W-30.45-12" Maple, N45W-39.97-7" Maple
- F-13) 1981 DNR LCRC, Liber 1, Page 622; Found and accepted Iron as recorded in Liber 1, Page 150. S18W-56.38-4" Maple, N53E-46.25-12" Maple, N03E-30.43-13" Maple, N32W-39.95-8" Maple

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- F-13) Quarter Section Corner common to Section 33, T24N, R7W and Section 4, T23N, R7W; Found Iron as recorded per Liber 1, Page 622. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**


- F-13) Set Missaukee County Monument on existing Iron
  - S30W 46.15 8" Oak in clump
  - S26E 60.38 20" Maple
  - N55E 46.13 16" Maple
  - N30W 40.00 12" Maple

Peer Group Reviewed and Approved

Date: 10-15-97

*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative

Signed by \_\_\_\_\_  
Surveyor's Michigan License No. 33977



Date 10-22-97