

**SURVEY &  
REMONUMENTATION**

#942

DEC 07 1994

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 290 PAGE 19

For corners in **COMMISSION**

<u>Missaukee</u> <small>(County)</small>	Located In:	Corner Code <u>##</u>
1. Public Land Survey	T <u>24N</u> R <u>7W</u>	<u>G-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

MISSAUKEE COUNTY MICHIGAN

RECORDED **OCT 28 1994** 1:15 PM

*Carolyn Flor*  
REGISTERED

Register of Deeds Stamp & File Number

I, J. Dean Geers, in a field survey on July 24, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- G-7) 1852 GLO Section post by Whelpley, Deputy Surveyor  
Beech 18 S 36 1/2 W 32, Beech 16 S 47 E 32, Beech 16 N 12 1/4 W 23
- G-7) 1909 Cavanaugh, County Surveyor: Gas pipe in concrete  
Corner Post S 45 3/4 E 46, Corner stake N 46 1/2 E 94
- G-7) 1979 Roser, Liber 1, page 630: Found 1909 Cavanaugh monument and raised with 7/8" x 20" rero

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-7) Section corner common to Sections 15, 22, 16 and 21

Found 1/2" Iron over 1" pipe per 1909 Cavanaugh survey. This corner is accepted as a careful and faithful perpetuation of the position of the original corner. Corner is ±2' West of North-South road Centerline.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7) Found 1" pipe and raised with 1/2" Iron and Missaukee County monument in monument box

- N 82 W - 64.57 - Power Pole
- S 60 W - 70.73 - 12" Spruce
- S 54 E - 76.44 - 10" Red Pine
- S 34 E - 97.13 - Power Pole

Peer Group Reviewed and Approved

Date: 10-26-94  
*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative



Signed by *J. Dean Geers* Date 9/28/94

Surveyor's Michigan License No. 33977