

SURVEY & REMONUMENTATION

JAN 16 1998

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

| | | |
|------------------------------------|--------------------------|---------------|
| <u>Missaukee</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>24</u> NR <u>7W</u> | <u>G-13</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

#1172

LIBER 314 PAGE 1253

MISSAUKEE COUNTY MICHIGAN

RECORDED NOV 10 1997 4:30 PM

Paulyn Flare
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, J. Dean Geers, in a field survey on June, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- G-13) 1838 GLO Section Post by John Brink, Deputy Surveyor; Beech 9-N21½W-46, Beech 9-N61½E-35
- G-13) 1909 Cavanagh County Surveyor; Set Gas Pipe in concrete; Sugar 6-N32E-63½, Sugar 6-N22½E-96½
- G-13) 1973 Erickson-Wilcox LCRC, Liber 1, Page 154; Found 1" Pipe 15" below surface. Raised with 1/2" Iron. N 30E-41.44-26" Maple, N30W-45.25-4" Elm, S40E-40.00-Sign Post
- G-13) 1981 DNR LCRC, Liber 1, Page 624; Found Cavanagh Monument and Iron as recorded in Liber 1, Page 154. N37E-41.46-28" Maple, N58W-45.19-6" Elm, N27E-63.5-28" Maple, North-33'-Cedar Post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-13) Section Corner common to Sections 33 and 34, T24N, R7W and Sections 3 and 4, T23N, R7W; Found Iron as recorded in Liber 1, Page 624. Corner is ±7' North of centerline of road East-West. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


- G-13) Set Missaukee County Monument on existing Iron
 - N60W 45.48 12" Elm
 - N35E 41.42 30" Maple
 - S45W 80.53 10" Spruce
 - N35W 57.34 8" Aspen

Peer Group Reviewed and Approved

Date: 10-15-97

J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by _____
Surveyor's Michigan License No. 33877



Date 10-22-97