

SURVEY & REMONUMENTATION

MAY 28 1997

LIBER 308 PAGE 682

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1051

For corners in Missaukee (County) Located In: _____ Corner Code # _____

1. Public Land Survey	T	<u>24N</u>	R	<u>7W</u>	<u>1-7</u>	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
2. Property Controlling in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____
3. Miscellaneous Property in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____

MISSAUKEE COUNTY MICHIGAN
 RECORDED **DEC 20 1996** *JMS*
Carolyn Flare
 REGISTER
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, J. Dean Geers, in a field survey on December, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-7) 1852 GLO Quarter Section post by Whelphey, Deputy Survey; Sugar 16-S34½W-15, Hemlock 24-S55½E-34, Ironwood 8-N61 3/4E-37
- I-7) 1909 Cavanagh survey notes; gas pipe in concrete, Tel. Pole-S62½W-68, Corner Fence Post-N51E-68½
- I-7) 1979 DNR LCRC, Liber 1, Page 632; Found 1" pipe with stones 1.5' deep from Cavanagh wit. Raised with ½"x18" rod, P.P.-S15E-123.97, P.P.-S72E-101.45, center pipe road sign-N35W-50.45 corner is ±2' South East-West centerline

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-7) Section corner common to Sections 14, 15, 22 and 23, T24N, R7W. Found ½" Iron of record in centerline of East-West Road. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-7) Set Miss. Co. Mon. on existing iron
 N29E - 84.38' - 24" Elm
 N29W - 95.71' - 6" Elm
 S20W - 81.44' - 3" Elm
 S20E - 79.08' - 5" Elm

Peer Group Reviewed and Approved
 Date: 12-19-96
J. Dean Geers
 J. Dean Geers, Missaukee Co. Representative

Signed by _____ Date 12-19-96
 Surveyor's Michigan License No. 3977

