

JAN 16 1998

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION For corners in

# 1174

LIBER 314 PAGE 1255  
MISSAUKEE COUNTY MICHIGAN  
RECORDED NOV 10 1997 4:30 p.m.

*J. Dean Geers*

Register of Deeds Stamp & File Number

Missaukee (County)	Located In:	Corner Code #
1. Public Land Survey	T 24N R 7W	1-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, J. Dean Geers, in a field survey on June, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- I-13) 1838 GLO Section Post by John Brink, Deputy Surveyor; Beech 8-N49W-39, Beech 8-N71E-34
- I-13) 1909 Cavanagh County Surveyor; Set Gas Pipe in concrete; Cedar Stake-S40W-58, Sugar Stake-N40E-48
- I-13) 1977 McClung LCRC, Liber 1, Page 568; found 3/4" Pipe. N45E-74.10-16" Maple, N40W-56.20- 8" Pine
- I-13) 1981 DNR LCRC, Liber 1, Page 622; Found 3/4" Pipe; S60W-40.47-P. Pole, N34W-63.50-5" Red Pine, N50E-73.90 18" Maple, S45E-47-Cedar Post
- I-13) 1995 Wilcox Survey, Liber S-3, Page 343; Found 3/4" Pipe as recorded in Liber 1, Page 622
- I-13) 1997 Kiiskila LCRC, Liber 1, Page 1124; Found DNR Corner of Record S47E-63.20-12" Red Pine, S64W-40.49-Power Pole Stub, N25W-77.27-13" Red Pine, N52E-73.92-14

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-13) Section Corner common to Sections 34 and 35, T24N, R7W and Sections 2 and 3, T23N, R7W; Found 3/4" Pipe as recorded in Liber 1, Page 622. Corner is in centerline of road North-South and ±5' South of centerline East-West road. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-13) Set Missaukee County Monument on existing Pipe
  - S58W 40.53 Power Pole Stub
  - S54E 59.68 16" Red Pine
  - N53E 73.86 16" Maple
  - N60W 78.38 16" Red Pine

Peer Group Reviewed and Approved

Date: 10-15-97  
*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative

Signed by \_\_\_\_\_  
Surveyor's Michigan License No. 33977

Date 10-22-97

