

SURVEY & REMONUMENTATION

JAN 16 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>24</u> NR <u>7W</u>	<u>J-13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

#1175
LIBER 314 PAGE 1256
MISSAUKEE COUNTY MICHIGAN
RECORDED NOV 10 1997 4:30 P.M.
Pauline Flare
REGISTER
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, J. Dean Geers, in a field survey on June, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													


- A. Description of original monument and accessories and/or subsequent restoration:
- J-13) 1838 GLO Quarter Section Post by John Brink, Deputy Surveyor; Beech 13, Quarter Section Corner
 - J-13) 1909 Cavanagh County Surveyor; Set Gas Pipe in concrete; Sugar 3-SW-80½, Beech 5-NW-99
 - J-13) 1979 Wilcox LCRC, Liber 1, Page 573; Found 5/8" Pipe, S63W-72.04-Telephone Pole, N50W-61.00- 26" Maple, N33E-46.20-3" Maple, S18E-61.70-Stop Sign
 - J-13) 1981 DNR Survey; Found 1/2" Pipe ±3' North of East-West road centerline and Found Iron Rod ±18' South of Pipe
 - J-13) 1993 Missaukee Surveying & Engineering Survey; Found 3/4" Pipe as recorded in Liber 1, Page 573
 - J-13) 1997 Kiiskila LCRC, Liber 1, Page 1122; Found 1/2" Pipe as recorded in Liber 1, Page 573; S60W-72.00-Telephone Pole, N50W-61.00-32" Maple, N30E-46.20 -8" Maple, S30W-88.10-8" Red Pine

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- J-13) Quarter Section Corner common to Section 35, T24N, R7W and Section 2, T23N, R7W; Found 3/4" Pipe as recorded in centerline road East-West. This corner is accepted as a careful and faithful perpetuation of the position of the original corner. The Iron found ±18' South was not accepted or utilized in this survey.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- J-13) Set Missaukee County Monument on existing Pipe
 - S62W 72.10 Telephone Pole, Found Nail
 - S31W 88.19 8" Red Pine, Found Nail
 - N06E 33.01 Found Iron
 - N48W 61.12 30" Maple, Found Nail
 - N34E 46.23 8" Maple, Found Nail

Peer Group Reviewed and Approved
Date: 10-15-97
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by _____
Surveyor's Michigan License No. 33977 No. 33977



Date 10-22-97