

# SURVEY & REMONUMENTATION

**JAN 16 1998**

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**  
For corners in

#1178  
**LIBER 314 PAGE 1259**

<u>Missaukee</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>24</u> N R <u>7</u> W	M-13	
	T <u>   </u> R <u>   </u>	<u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>	<u>   </u>

MISSAUKEE COUNTY MICHIGAN  
RECORDED NOV 10 1997 4:30 P.M.  
*Paula Klare*  
REGISTER  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, J. Dean Geers, in a field survey on June, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		13		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- M-13) 1838 GLO Township Corner Post by John Brink, Deputy Surveyor; Beech 8-N67W-41, Beech 16-S52E-15
- M-13) 1909 Cavanagh County Surveyor; Set Gas Pipe in concrete; Sugar 6-N37 3/4 E-81; Beech 6-N35 1/2 W-69 1/2
- M-13) 1972 L. Cavanagh Survey, Liber S-1, Pages 24-27; Set 1/2"x18" Bar from one 1909 Cavanagh witness
- M-13) 1981 DNR LCRC, Liber I, Page 634. Found and accepted 1/2" x18" Rerod set by L. Cavanagh Survey in Section 36, Liber S-1 Pages 24-27. Replaced Found Rerod with 5/8"x36" Rerod; N30W -26 Beech-44.53; S50W-6 Maple-53.68; S22E-28-Maple-61.40; N45E-Cedar Post-47

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**


- M-13) Section Corner common to Section 1, T23N, R7W, Section 36, T24N, R7W, Section 31, T24N, R6W and Section 6, T23N, R6W. Found Iron as recorded in Liber 1, Page 634. Corner is in centerline of East-West road. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- M-13) Sct Missaukee County Monument on existing Iron
  - S45E 47.77 3" Maple
  - N27W 45.97 20" Maple
  - N20E 53.43 4" Basswood
  - S62W 47.01 16" Maple

**Peer Group Reviewed and Approved**  
Date: 10-15-97  
*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative

Signed by \_\_\_\_\_  
Surveyor's Michigan License No. 3817 No. 33977



Date 10-22-97