

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
Missaukee Located In Corner Code #  
 (County)

1. Public Land Survey T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
 in Section S 17 T 24N R 7W 7  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
 Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on April 25, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
7 - LCRC #632 - C. F. Roser - 1981 - Set 5/8" x 36" rered with RLS cap in roots of SW edge of  
 12" Maple stp. and Cedar post with location tag  
 9" Maple N53°W 15.1'  
 9" Maple N10°E 26.9'  
 23" Maple N60°E 73.9'  
 N-S trail due East 100'±

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

7 - N. 1/16 Corner common to sections 16 & 17, T24N, R7W - Found 5/8" x 34" rebar, up 1.2' with broken RLS cap (C. F. Roser) and two witnesses. Replaced broken RLS plastic cap with stamped 2" Aluminum cap on original rebar. Drove rebar down. 2" Aluminum cap on 5/8" rebar is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

7 - 2" stamped Aluminum cap on 5/8" x 34" rebar.  
 N7°E 27.54' to set N & T in W. side 14" Sugar Maple (CFR)  
 N82°E 19.92' to set N & T in N. side 8" Oak  
 S45°W 37.41' to set N & T in NW side 5" Oak  
 N54°E 74.78' to set N & T in NW side 28" Sugar Maple (CFR)  
 Set Blue Carsonite Post with location tag 1' NE

