

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 N.R. 8 W


Missaukee COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 14-15-23-22

CORNER MONUMENT Left 2"x2" Angle iron in place

DATE MONUMENT PLACED AND WITNESSED August 3, 1961

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

20" Basswood - N2W - 81.7 feet

14" Elm - N74E - 89.1 feet

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey of Section 14. Found 2"x2" angle iron in place in center of E-W road and in line with fence north and old road grade south. Appeared acceptable as section corner, no evidence to the contrary. Probably established in 1909 Gavanagh survey.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostling DATE 8/7/61
REGISTERED LAND SURVEYOR