

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 N.R. 8 W


Missaukee COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 14 and 15

CORNER MONUMENT 1" pipe with 4" Aluminum cap

DATE MONUMENT PLACED AND WITNESSED August 3, 1961

WITNESSES TO CORNER.....



24" W. Pine stump - N72W - 68.3 feet

20" W. Pine stump - S26E - 77.0 feet

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored at what was concluded to be Teed's location in 1901 survey of Section 14. Set corner from the only large stump near that would place corner in conformity with a proper pattern of survey. Also, found what appeared to be evidence of an ancient post when digging for corner. Checks for distance both north and south.

SURVEYOR'S SEAL

SIGNED Kenneth Ostling DATE 8/7/61
REGISTERED LAND SURVEYOR