

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 N.R. 8 W


Missaukee COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 11-12-13-14

CORNER MONUMENT 1" pipe with 4" Aluminum cap

DATE MONUMENT PLACED AND WITNESSED August 3, 1961

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

20" W. Pine - S61W - 16.8 feet

Only witness suitable

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored at a point prescribed by the testimony of a local resident of the SW 1/4 of Section 12, Mr. Mark Hoel, who recalled a squared scribed stake at this location first recalled in 1939. Checks for line over 1/4 and section corner south. A large W. Pine nearby to which the corner could be referenced makes for fairly accurate restoration of this corner. This method was considered more justified than double proportionate measurement since it conforms more with present occupation and local acceptance.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostling DATE 8/7/61
REGISTERED LAND SURVEYOR