

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 N.R. 8 W


Missaukee COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 14 and 23

CORNER MONUMENT Drove 1"x24" pipe, below surface

DATE MONUMENT PLACED AND WITNESSED August 3, 1961

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

36" W; Pine stump - N2W - 47.4 feet

Steel fence post - S4W - 29.5 feet

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by reference to line and measurements over 1/8 and section corners both east and west. Set corner to make equal 1/4 miles in west 1/2 mile, but on line over 1/8 and section corners east. This conforms most closely with record measurements of previous surveys, while making the least departure from existing monumentation on this mile. This point falls in line with fences running north and south. Would place the east 1/8 corner on line but 1.2 feet west of its proper position, also would place the west 1/8 corner at midpoint but 1.5 feet north of its proper position. Unable to locate any previous monument which was probably removed in road construction as were the original BTs.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostling DATE 8/7/61
REGISTERED LAND SURVEYOR