

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 24N N.R. 8 W


Missaukee COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 10-11

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 6-27-67

WITNESSES TO CORNER.....



20" R. Pine N 33 E 59.3"

24" R. Pine N 9 W 42.0"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement between section corners. Could not find Fargo pipe or witnesses, although our measurement checks Fargo record for entire mile.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Rothig* DATE 6-29-67  
REGISTERED LAND SURVEYOR #10068