

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 N.R. 8 W


Missaukee COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 15-22

CORNER MONUMENT Set 1" pipe with 4" aluminum cap below surface

DATE MONUMENT PLACED AND WITNESSED 5-24-67

WITNESSES TO CORNER.....



5" W. Pine N 41 W 64.0'

6" S. Maple N 49 E 67.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored during retracement in this township. Found 3/4" pipe below road as established and supported by Teed's survey and witnesses of record. Best available evidence.

Old post also found when setting corner.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE 6-15-67
REGISTERED LAND SURVEYOR #10068