

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 N.R. 8 W


Missaukee COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 15-16-21-22

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 5-25-67

WITNESSES TO CORNER.....



6" Tw. S. Maple N 23 E 13.2'

18" Cedar stp S 47 E 22.4'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored during a retracement in this township. Set corner at old fence corner post which was considered best available evidence. Corner falls at edge of swamp as called for in U.S. record and is almost exactly on line over 1/4 and section corner east, and at double distance. Unable to locate corner or witness called for in County survey of record. Believe this to be position for corner, based on supporting evidence.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostling DATE 5-25-67
REGISTERED LAND SURVEYOR #10668